

**2023 MAINTENANCE AND REPAIR PROGRAM
PILESGROVE TOWNSHIP
PROJECT NO. 2023-01
PAGE 1 of 2 – BASE BID**

No.	Road Name	Length Miles	Length Feet	Avg. Width	Area Sq. Yds.	Type Bit. Mat'l.	Rate	Est. Gallons	Kind Cover Mat'l	Lbs per Sq. Yd.	Estimated Total Tons
1	Sharptown Auburn Road Featherbed Lane Including Intersection to wide spot Wide spot to end of wide spot wide spot to rt40	.97	See below See below 2562 1070 4468	22' 26' 23'	6263 3091 11418	CRS-M2 CRS-M2 CRS-M2	0.43 0.43 0.43	2693 1329 4910	#7 washed stone #7 washed stone #7 washed stone	32 32 32	100 49 183
2	Melissa Lane From Entrance to Loop Loop	.57	See below 694 2310	40' 36'	3084 9240	CRS-M2 CRS-M2	0.45 0.45	1388 4158	5/16 Stone 5/16 Stone	25 25	39 116
3	Catalpa Crest Marlton Road to Marlton Road Catalpa Place Catalpa Crest to End	.39	1657 380	28' 24'	5155 1013	CRS-M2 CRS-M2	.45 .45	2320 456	5/16 Stone 5/16 Stone	25 25	64 13
4	Robbins Road Commissioners Pike to Yorketown Road	1.2	6444'	23'	16468	CRS-M2	0.43	7081	#7 Washed	32	263
Totals:			19,585		55,732			24,335			See below
Surface Preparation (4 feet wide both sides)						SY	17,409				
Cutback Asphalt (CRS-2M Oil)						GAL	24,335				
#7 Washed stone						TONS	595				
5/16 Stone						SY	37,240				
						TONS	232				
						SY	18,492				