

**2023 MAINTENANCE AND REPAIR PROGRAM
 PILESGROVE TOWNSHIP
 PROJECT NO. 2023-01
 PAGE 2 of 2
 ALTERNATES**

<u>No.</u>	<u>Road Name</u>	<u>Length Miles</u>	<u>Length Feet</u>	<u>Avg. Width</u>	<u>Area Sq. Yds.</u>	<u>Type Bit. Mat'l.</u>	<u>Rate</u>	<u>Est. Gallons</u>	<u>Kind Cover Mat'l</u>	<u>Lbs per Sq. Yd.</u>	<u>Estimated Total Tons</u>
Alt # 1	Cedar Lane Fenwick RD to Old Salem RD	.90	4770'	22	11660	CRS-M2	0.45	5247	#8 Washed	23	134
Alt # 1	Totals:				11660			5247			134
	Surface Preparation					SY		4240			
	Cutback Asphalt (CRS-2M Oil)					GAL		5247			
	#8 Washed stone					SY		11660			
						TONS		134			